

JESCO Farm Drainage Tileplow

www.tileplow.com

LWB Model



Model: LWB-6B Install 5" or 6" tile with the 6" boot kit **\$14,200**

- Pulled by a 4wd tractor. (27,000lbs suggested. weight)
- Twin hydraulic cylinders with one pair of quick connects.
- Available for pickup in Des Moines or Fairbank, IA.
- Optional boots are available for 3" & 4" tile.
- Manufactured in the State of Iowa with products from the USA.
- Hydraulic cylinders made in the USA.
- We supply quality products that are made in a manufacturing facility, not a welding shop.
- Powder coat paint for long durability.
- CAD/CAM technology utilized through-out the production process.
- Chain depth gauge included.

515-309-9884

scott@tileplow.com

JESCO AG LLC.

Specifications	Value	Comment
Weight	7200 lbs	With Cylinders and hoses
Width -		
Tire track outside-to-outside	129"	
Transport width on-trailer	94"	Walking beam removed
Length - Tongue to boot	20'	
Height	9'-2"	GPS mount may be removed, subtract 6"
Depth	58"	Working depth
Hitch	Cat III drawbar	
Hitch Pin requirement	1.5"	Pin not supplied
Tire/wheel Quantity	4	
Tire size	385/65Rx22.2	Used Truck tires – Exact tire specs vary
- Pressure	100 PSI	
- Load rating	Load J	Load J minimum
- Ply rating	18 Ply	
Wheel size (4)	22.5x11.25"	8-8-6 wheels with nuts
Wheel rating	AG type, 9000lbs/ea	
Hydraulic cylinders	2	Made in the USA, from US components.
- Required remotes needed	1 set	
- Size	4"x24"	
- Hoses	ISO Ag connectors	Parker hoses, made in the USA
Laser/GPS mast mount	Included	
4B-KIT boot	3"-4" tile	One included in the LWB price.
6B-KIT boot	5"-6" tile	One included in the LWB price.

Call 515-309-9884

scott@tileplow.com

www.tileplow.com

JESCO AG LLC.